



Summary and Next Steps  
Structural Review no. 7 by Williams Engineering  
May 24, 2017

Purpose of Review:

- Confirm the Ross River School remains safe to occupy.

Evaluation method:

- The structural engineer walked through the school. He looked for areas that might show that the building has moved.
- The engineer also took measurements to compare to previous reviews.
- For part of the walk-through, the school principal and school safety officer were present.

Conclusions:

- The school is safe to occupy.
- Relevel the school soon.

Recommendations:

- Relevel the school in summer 2017.
- Relevel the mechanical room and mezzanine.
- Strengthen load-bearing walls.
- Open the window header in the kindergarten classroom to look at the framing.
- Complete another structural review in late July 2017.

Next steps:

- Yukon government is looking at releveling the school in summer 2017.
- We are looking at options for tackling the other recommendations.